Greg's Excavating, LLC
151 ROUTE 87
COLUMBIA CT 06237
860-617-5078

Silt fence
remove loam/organic Layer from driveway & fill area
Remove trees & stump from driveway area

40' of 18" ADS HDPE
26' of 12" ADS HDPE

12' wide driveway

Bank run gravel to be used for Fill area

Fill area to be less than 8% with 3 to 1 side slopes

Install 8" depth of 4" minus gravel with 4" depth of processed gravel base

Paved apron to meet town spec

Loam shoulders, rake, seed, mulch

