

May 25, 2021

Remington & Vernick Engineers  
922 Fayette Street  
Conshohocken, PA 19428

RE: PH 1 – Relining  
Change Order Request CO #1 – Cleaning at Reed Street

Dear Mr. Zelinsky,

Thanks for talking with me today regarding the specialty cleaning on-site. After some investigation we firmly believe that the valves entering the bay are no longer working properly. This causes sand and water to wash into the pipes during high-tide. It's believed that a large storm may have come in and buried the pipes partially under sand causing backups and flooding. We always expected some silt and debris on these line segments since our last mobilization, but the problems above have caused for far more cleaning than anticipated.

We formally request to be paid 3 days for heavy cleaning the line segments above due to the flooding from the pipes @\$3,400 per day, or \$10,200

To best repair the three outfalls we would recommend installing a coffer dam around the 3 pipe locations and excavate the sand slightly below the invert of the pipes. While this is being performed, we will clean and televise the outfall pipes. After all silt has been removed, we will stabilize the area by installing an underwater barrier using riprap R-5 or R-6 around the three pipes to protect the area from erosion.

Total cost to perform the outfall cleaning.....@\$26,400 Lump Sum

Let me know if you have any questions or concerns.

Sincerely,

Matt Zakutny  
Director of Project Management

# SPS *Standard Pipe Services*

**Services Performed By:**  
Standard Pipe Services, LLC  
563 Walther Road  
Newark, DE 19702  
P: 302-368-7414  
F: 302-737-3034

**Services Performed For:**  
Remington & Vernick Engineers  
922 Fayette Street  
Conshohocken, PA 199428  
Contact: Kevin Zelinsky  
Email: Kevin.Zelinsky@rve.com  
P: 610-940-1050  
F: 610-940-1161

WE PROPOSE HEREBY TO FURNISH MATERIAL AND LABOR COMPLETE IN ACCORDANCE WITH SPECIFICATIONS BELOW, FOR THE SUM OF: **DOLLARS: \$26,400**

Payment to be made as follows: **Net 30 days**

**Job Title: Outfall Repairs**

**Job Location: Dewey Beach, DE**

*We hereby submit specifications and estimate for:*

Price is to repair three outfalls on the bay side of Read Avenue by installing a coffer dam around the 3 pipe locations and excavate the sand slightly below the invert of the pipes. While this is being performed, we will clean and televise the outfall pipes. After all silt has been removed, we will stabilize the area by installing an underwater barrier using riprap R-5 or R-6 around the three pipes to protect the area from erosion.

Total cost to perform the outfall cleaning.....@\$26,400 Lump Sum

Work to be performed to your schedule with a minimum of one day notice.

Authorized Signature: \_\_\_\_\_

**Matthew J. Zakutny**

**Date of Proposal:** *June 8, 2021*

**ACCEPTANCE FOR PROPOSAL:** The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above. I/We understand the proposed prices does not include a prevailing wage component.

**Date of Acceptance:** \_\_\_\_\_ **Signature:** \_\_\_\_\_

PROPOSAL OF WORK